Eexpenses necessary to be incurred for the Construction of 3 Nos of Toilets at Grade 06 in Fathima Balika Maha Vidyalya Puttalam.

S/1	Description of work	Unit	Qty	Rate	Amount	
1	Excavation in trenches for walls column pits in ordinary soil from 0'0" to 5'0" deep and depositing excavated material not exceeding 30'0"	m³	5.5	2,445.00	13,447.50	
2	2" thick Cement Concrete screed 1:3:6 (1 1/2) in foundation at depth not exceed in 5' 0"	m²	11.75	1,877.00	22,054.75	
3	Cement concrete 1:2:4(3/4") in 9" X 6" Beams Upto 1st floor level	L.m	20	1,542.00	30,840.00	
4	Filling under floors including levelling, watering & compacting in 3" layers with imported gravel	m³	2.25	3,082.00	6,934.50	
5	4*Thick hollow block work in cement and sand mortar 1:5 with cavities unfilled.	m²	47.5	2,168.00	102,980.00	
6	5" Thick R.C.C 1:2:4(3/4") floor slab in 1st floor	m²	10	4,396.00	43,960.00	
7	Tor steel reinforcement to lintels, slabs, beams or columns bent to shape, laid in position and tied with G.I. Wire as directed.	kg	77.5	329.00	25,497.50	
8	Sawn timber formwork for underside of first floor slab	m²	12	1,548.00	18,576.00	
9	3" Thick cement concrete 1:2:4(3/4")- in Floor concrete	m²	4.25	3,876.00	16,473.00	
10	5/8° thick to wall in cement and sand 1:5 finished semi-rough with wooden float.	m²	58.5	1,348.00	78,858.00	
11	Plinth plastering 1:3 cement sand mix finished with cement floting	m²	8	1,575.00	12,600.00	
12	Supplying & fixing of Cladding Door	Nos	3	26,000.00	78,000.00	
13	Supplying &placing of concerte fanlight	Nos	3	1,750.00	5,250.00	
14	Supplying & laying of Squatting pan	Nos	3	4,500.00	13,500.00	
15	Applying of Two coats of filler	lit	20	445.00	8,900.00	
16	Painter wages	Item	Allow	Sum	5,000.00	
17	Construction of 8' x 5' x 6' Soakage pit with cover slab	Nos	1	110,000.00	110,000.00 592,871.25	
	Total Civil Cost					
	Contoingencies 3% Total Estimated Cost					
	610,657.39					

Prepared By..

M.W.M. ALI BISRI
ENGINEERING DRAUGHTSMAN
NO. 66, U.C.O., POLES ROAD,
PUTTALAM.

Eexpenses necessary to be incurred for applying of paint (5 Nos of Class room) at Grade 06 in Fathima Balika Maha Vidyalya Puttalam.

S/I	Description of work	unit	Qty	Rate	Amount
1	Preparing and apply one coat of Alkali resistant primer and two coats of emulsion paint to walls.	m²	650	824.00	535,600.00
2	Preparing and painting wood work with primer and 2 coats Enamel paint	m²	240	1,105.00	265,200.00
3	Apply of anticorrosive mat coating to chair & desk	m ²	15	930.00	13,950.00
	Total civil		814,750.00		
	Contingenc	24,442.50			
	Total Estima	839,192.50			

Prepared By:

no ecan

M.W.M. ALI BISRI
ENGINEERING DRAUGHTSMAN
NO. 66, U.C.Q. POLES ROAD,
PUTTALAM.

Expenses necessary to be incurred for the Construction of 45m length concrete road at Fathima Balika Maha Vidyalaya, Puttalam.

S/No	Description of work	Unit	Qty	Rate	Amount
1.	Filling under floors including levelling, watering & compacting in 3" layers with imported gravel	M ³	12.744	2,022.00	25,768.37
2	Mixing Concrete 1:2:4(3/4") in Road	M ³	23.5	27,227.00	639,834.50
- 40	Toital civ	665,602.87			
	Engineering & Ad	19,968.09			
	Contingen	19,968.09			
	Total Estima	705,539.04			

Prepared By:.....

M.W.M. ALL LISRI ENGINEERING DRAUGHTSMAN NO. 66, U.C.Q., FOLES ROAD, PUTTALAM.